

5-19 15-195-20894-00-00

6 031249

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-20,894
C E/2 E/2 SW, SEC. 7, T 11 S, R 22 W/E
1320 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

2970 feet from E section line

Operator: Ritchie Exp Inc
Name & Address: 125 N. Market Suite 1000
Wichita, Kansas 67202

Lease Name Buchholz Well C-1

County Trego 127.40

Well Total Depth 3920 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 190

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso License Number

Address Chase, Ks.

Company to plug at: Hour: AM Day: 19 Month: May Year: 19 89

Plugging proposal received from Mark

(company name) Kelso (phone)

were: 8 5/8 " set at 190' cwc w/140 sks. 4 1/2" set at 3918' w/200 sks. Perf 3534' - 3908'.
PBTD 3680'. Order sand and common cmt. Pull pipe. Order 225 sks 60/35 poz
10% gel 2% dicel 500# Hulls. Allied Cement Co. Wellbrock Water Truck.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1989
6-6-89

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 9:45AM Day: 19 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 3480' w/4 sks common cement on sand w/bailer.

One shot recovered 2700' of 4 1/2" casing. Squeezed 8 5/8" w/225 sks cement blend w/500 #
Hulls. To max psi 700%. Close in 200 psi. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 6-8-89
INV. NO. 25022

Signed Carl Goodrow (TECHNICIAN)