

3-26

4-031802

15-195-20827-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-195-20,827

S2 NW SE /4 SEC. 07 , 11 S , 22 W  
1650 feet from S section line  
1980 feet from E section line

Operator license# 4767

Lease Buchholz well # B-2

Operator: Ritchie Exploration, Inc.

County Trego

Address: 125 N. Market  
Suite 1000  
Wichita, Kansas 67202

Well total depth 3917 feet <sup>127.30</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 167 feet

Aband. oil well X, Gas well  , Input well  , SWD  , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 26 Month: March Year: 93

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone:

Were: Order 375 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Perf. shots in critical control areas for block squeeze  
at 1682' and 1157' to 1188' with 160 sx.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[   ], None[   ]

Completed: Hour: 8:45A.M., Day: 26, Month: March, Year: 93

Actual plugging report: 8 5/8" set @ 167' w/165 sx. cwc. 4 1/2" set @ 3909' w/150 sx. Prod. perf. @ 3492' - 3906'. Squeeze 8 5/8" w/100 sx. cement blend to Max. P.S.I. 300#. Close in P.S.I. 150#. Squeeze 4 1/2" w/275 sx. cement blend w/500# hulls mixed in to Max. P.S.I. 800#. Close in P.S.I. 150#. Plug completed.

Remarks:    
Condition of casing(in hole): GOOD X BAD   Anhy.plug: YES X NO    
Bottom plug(in place): YES  , CALC X, NO   Dakota plug: YES X, NO    
Plugged through TUBING  , CASING X. Elevation:

I did not observe the plugging. Carl Goodrow

**INVOICED**

DATE 4-2-93

(agent)

Form CP-2/3

INV. NO. 37551

RECEIVED STATE CORPORATION COMMISSION

APR -1-1993

CONSERVATION DIVISION Wichita, Kansas