

15-195-20866-00-01

4-032156

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,866

5-23

NE SE SE /4 SEC. 08, 11, 22 W
330 feet from S section line
990 feet from E section line

Operator license# 4767

Lease: Custer Well # A-1

Operator: Ritchie Exploration, Inc.

County: Trego

Address: 125 N. Market - Suite 1000
Wichita, Kansas 67202

Well total depth 3909 ^{127.04} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 23 Month: May Year: 1996

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone: -

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED

KANSAS CORPORATION COMMISSION

5-29-1996

MAY 29 1996

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00 P.M., Day: 23, Month: May, Year: 1996

Actual plugging report: 8 5/8" set at 208' cwc with 175 sxs. 4 1/2" set at 3904' with 125 sxs. Prod. Perfs. - 3320' - 3806'. PBD 3777'. Squeezed 1122' and 1138' with 200 sxs. Squeezed 4 1/2" w/180 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 700#. Close in P.S.I. 700#. Squeezed backside with 50 sxs cement blend to Max. P.S.I. 500#. Close in P.S.I. 200#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES 1649 NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING Elevation: 2197 GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

INVOICED
DATE JUN 11 1996
INV. NO. 45774
5-23

OKD