

15-195-21313-00-00

6070008

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21,313-00-00

E¹/₂-SW-SE, Sec. 8, T 11 S, R 22 W D

660 feet from N/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name THORNHILL Well # 2

Operator: A. SCOTT RITCHIE
Name & Address 125 N. MARKET, #950
WICHITA, KANS.
67202

County TREGO

Well Total Depth 3880 feet \$126.10

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 205

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor MURFIN DRUG. CO. License Number 6033

TRG # 604

Address 250 North. WATER, SUITE #300 WICHITA, KANS. 67202

Company to plug at: Hour: 4:00 AM Day: 23RD Month: SEPT. Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO LLOYD DELLETT.

(company name) MURFIN DRUG. CO. (phone) 913-567-4705

were: 8⁵/₈" - 205 FT SP. CUL. w/170^{SK} COMMON 2% GEL-3% CA-CL. (ALLIED)

ORDER 200^{SK} 50/50 Formix 6% GEL-3% CA-CL. AND 8⁵/₈" PLUG.

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

ARBUCKLE TOP @ 3870 FT, ELEV. 2197', ANH. 1652.

Signed Murfin Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:00 A.M. Day: 23RD Month: SEPT. Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 200^{SK} 50/50 Formix 6% GEL, 3% CA-CL. AND 8⁵/₈" PLUG.

SPOTTED WITH DRILL STEM, TURNED HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG @ 3840 FT w/20^{SK} CMT., 2ND PLUG @ 1670 FT w/20^{SK} CMT.

3RD PLUG @ 840 FT w/100^{SK} CMT. 4TH PLUG @ 270 FT w/40^{SK} CMT.

5TH PLUG ^{SOLID BRIDGE} HULLS-PLUG @ 40 FT w/0^{SK} CMT., 10 IN RAT HOLE (CIB)

Remarks: CEMENTED BY ALLIED CMT.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 10-11-83
INV. NO. 5728-20K

RECEIVED
STATE CORPORATION COMMISSION
10-3-1983
OCT 3 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed Murfin Schmidt
(TECHNICIAN)