

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22061-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 14-18S-8W
4950 feet from S Section Line, 1600 feet from E Section Line
Lease Name: SKILES Well #: 4
County: RICE Total Vertical Depth: 3300 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 3101 N ROCK RD STE 125
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3299		500 SX
SURF	8.625	286		200 SX

10.7.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2008 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 938-2537

Proposed Plugging Method: ACCORDING TO RULES AND REGULATIONS OF THE KCC.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 12/22/2008 12:40 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3100' & CAP WITH 5 SX'S CEMENT, PERFORATE @ 1100', 800' & 340'. RUN TUBING TO 1100 AND PUMP 35 SX'S CEMENT, PULL TUBING TO 800' & PUMP 35 SX'S CEMENT, PULL TUBING TO 340' & CIRCULATE CEMENT TO SURFACE. HARD CEMENT DOWN ABOUT 15' ON BACKSIDE OF 5 1/2" - TOPPED OFF WITH CEMENT.

Perfs:

Top	Bot	Thru	Comments
3176	3245		OA

INVOICED
DATE 1-27-09 313109
INV. NO. 200906118
2009061291

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-34057. LOG TECH TICKET 5570. PERFS @ 3176-3245.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Handwritten initials/signature