

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00791-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 16-17S-8W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: RATHBUN A Well #: 1
County: ELLSWORTH Total Vertical Depth: 3247 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3241	1326	75 SX
SURF	8.625	216		140 SX

105.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/17/2009 12:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/17/2009 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3190' AND CAP WITH 5 SX'S CEMENT. CUT CASING AT 1326' AND PULL OUT OF HOLE. RUN TUBING TO 1050' AND PUMP 15 SX'S GEL FOLLOWED BY 35 SX'S CEMENT AND COTTON HULLS. PULL TUBING TO 750' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 270' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 60' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3241	3247		OH

INVOICED

DATE 3-4-09
INV. NO. 2009061301

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 26 2009
CONSERVATION DIVISION
WICHITA KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET 35290

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

SK

PLO