

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00630-00-00
Spot: SWNENE Sec/Twnshp/Rge: 5-16S-10W
4290 feet from S Section Line, 1170 feet from E Section Line
Lease Name: VACEK B Well #: 1
County: ELLSWORTH Total Vertical Depth: 3357 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3356		NO SXS LISTED
SURF	8.625	307		NO SXS LISTED

109.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2009 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAVE WERTZ Witness Type: NONE
Date/Time Plugging Completed: 02/10/2009 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3280' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1300', 1000', AND 350'. RUN TUBING TO 1300' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 1000' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 350' AND CIRCULATE CEMENT TO SURFACE. PULL OUT TUBING AND TOP OFF. USED APPROX. 265 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3330	3334		

INVOICED

DATE 3-4-09
INV. NO. 2009061301

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 26 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-35286.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK

PKS