

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20457-00-00
Spot: NENENE Sec/Twnshp/Rge: 5-16S-10W
4851 feet from S Section Line, 471 feet from E Section Line
Lease Name: VACEK B Well #: 5
County: ELLSWORTH Total Vertical Depth: 3330 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3297		125 SXS CMT
SURF	10.75	325		200 SXS CMT

108.23

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/13/2009 9:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 02/13/2009 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU AND RUN TUBING TO 3150' AND PUMP 50 SX'S CEMENT WITH 200#'S COTTON HULLS. PERFORATE AT 1300', 1000', AND 375'. RUN TUBING TO 1300' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 1000' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 375' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECT ON TO BACKSIDE OF 7" CASING AND PUM 130 SX'S CEMENT. USED 400 SX'S TOTAL/

Perfs:

Top	Bot	Thru	Comments
3272	3283		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 26 2009
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 3-4-09

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET # C-35288.

INV. NO. 2009061301

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PKT