

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-00445-00-01
Spot: NENW Sec/Twnshp/Rge: 5-15S-2W
4611 feet from S Section Line, 3342 feet from E Section Line
Lease Name: STAHL Well #: 1
County: SALINE Total Vertical Depth: 3229 feet

Operator License No.: 6819
Op Name: SCOTT'S WELL SERVICE INC
Address: PO BOX 136
ROXBURY, KS 67476

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3221		
SURF	8.625	171		

104.94

Well Type: SWD UIC Docket No: E21490.1 Date/Time to Plug: 02/12/2009 10:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: JAY SCOTT Company: SCOTT'S WELL SERVICE Phone: (785) 254-7828

Proposed Plugging Method: (WELL HAD 2 3/8" FIBERGLASS TUBING BROKE OFF @ 365' W/CEMENT ON BACKSIDE) PUMP BOTTOM PLUG THROUGH TUBING AND PACKER AT 360'. RUN 1' DOWN BACKSIDE TO CIRCULATE TO SURFACE. RUN TUBING IN 4 1/2" TO CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: NONE
Date/Time Plugging Completed: 02/12/2009 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

RAN 2 3/8" TUBING (DOWN 4 1/2") WITH PACKER AND SET PACKER AT 360' AND PUMPED 80 SXS CEMENT. RAN 1" TUBING TO 290' ON THE BACKSIDE AND TAGGED CEMENT. PUMPED 125 SXS TO CIRCULATE TO SURFACE. RAN 2 3/8 BACK DOWN 4 1/2" TO 360' AND PUMPED 40 SXS AND CIRCULATED TO SURFACE.

Perfs:

INVOICED
DATE 3-4-09
INV. NO. 2009061307

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 26 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENTING TICKET #20108 TOTAL 245 SXS 60/40 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

JK

PBT