

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23423-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 5-8S-20W  
1520 feet from N Section Line, 890 feet from W Section Line  
Lease Name: BENOIT THYFAULT Well #: 1-5  
County: ROOKS Total Vertical Depth: 3459 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	43		100 SX
PC	5.5	1506		
PROD	5.5	3452	0	240 SX 112.42
SURF	8.625	212	0	150 SX
T1	2.875	3425		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2009 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: ANDREW C. NOONE Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 210 sxs 60/40 pozmix - 4% gel - 400# hulls - 14 sxs gel spacer.  
Port collar at 1506' w/180 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/24/2009 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Pumped 50 sxs 60/40 pozmix - 4% gel with 400# hulls and 14 sxs gel spacer - followed with 125 sxs 60/40 pozmix - 4% gel.  
S.I.P. 250#.  
8 5/8" - pumped 5 sxs 60/40 pozmix - 4% gel.  
S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3358	3366		
3257			
3250			
3214	3222		

**INVOICED**  
DATE 3-12-09  
INV. NO. 2009061312

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 06 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT SERVICES, INC.-TICKET #15832.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

Pat Bedore  
(TECHNICIAN)

CM

MAR 04 2009

PKT

BAIRD OIL CO LLC  
LOGAN KS 67646

5-08S-20W  
1520' FNL & 890' FWL, SEC

#1-5 BENOIT / THYFAULT

site: 1-3/4 E OF NICODEMUS KS      city: ROOKS      API 15-163-23423  
contr: MURFIN DRILLING #16      field: NICODEMUS SE EXT (1/2 SE)  
opd: GARY GENSCH  
fr date 08/17/2004      spd date 11/17/2004      drig comp 11/25/2004      card issued 12/20/2004      last revised 12/20/2004


ELV: 1957 KB, 1952 GL  
tops.....depth/datum  
PBTD .....3429 -1472  
RTD.....3459 -1502  
NO TOPS RPTD

IP status:  
OIL, LKC, INTV NA, 12/07/2004  
CSG: 8-5/8" 212 (ALT 2), PROD CSG NA, MULTI STAGE  
COLLAR AT 1506 / 180 SX  
COMMENT: MI & RURT 11/17/2004  
NO CORES  
DSTS TAKEN - DETAILS NA  
TRGT ZN: LKC, ARB (OIL), PTD 3500 (ARB), MICT - CO, PB  
3429, PF (LKC) INTV NA, AC'D, SWB LD, SO, POP, OIL  
WELL (POTENTIAL NOT RPTD), 12/7/2004 - TIGHT HOLE -  
NO OTHER INFO AVAILABLE - TEMP COMP 12/20/2004

COPYRIGHT 2004  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS