

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21240-00-00
Spot: SWSESE Sec/Twnshp/Rge: 11-32S-20W
329 feet from S Section Line, 824 feet from E Section Line
Lease Name: K AND G Well #: 1
County: COMANCHE Total Vertical Depth: 5284 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4950		WITH 2 SX CMT
COND	20	55		WITH 5 YDS CMT
PROD	4.5	5274	3935	WITH 150 SX CMT
SURF	8.625	756		WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/24/2009 9:50 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 4950' WITH 2 SX CMT. PLUG AT 800' WITH 15 SX GEL & 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2009 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4950' WITH 2 SX CMT. 1ST PLUG AT 800' WITH 15 SX GEL, 100# HULLS, & 50 SX CMT. 2ND PLUG AT 250' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5118	5128		

INVOICED
DATE 3-12-09
INV. NO. 2009061313

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 03 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY GRESSEL OIL FIELD SERVICES.

Plugged through: CSG

District: 01

RECEIVED
FEB 25 2009
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form Ch