

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22870-00-01
Spot: NESE Sec/Twnshp/Rge: 9-30S-11W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: CONNORS TRUST Well #: 1
County: BARBER Total Vertical Depth: 3929 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1551 N WATERFRONT PKWY STE 150
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2880		WITH 2 SX CMT
PROD	4.5	3928	2050	WITH 300 SX CMT
SURF	8.625	335		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/17/2009 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 2900' WITH 2 SX CMT. PLUG AT 720' WITH 15 SX GEL, 300# HULLS & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2009 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2880' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN CASING & RAN IN WITH 2 3/8" TBG TO SPOT PLUGS THROUGH. 1ST PLUG AT 720' WITH 15 SX GEL & 50 SX CMT. 100# HULLS IN WITH CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 100# HULLS IN WITH CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2636	2643		

INVOICED
DATE 3-12-09
INV. NO. 2009061314

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 03 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
FEB 25 2009
KCC DODGE CITY

Signed Stephen J Pfeifer
(TECHNICIAN)