

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25244-00-00
Spot: SENWSENW Sec/Twnshp/Rge: 29-19S-12W
1810 feet from N Section Line, 1660 feet from W Section Line
Lease Name: SCHARTZ CPC Well #: 1-29
County: BARTON Total Vertical Depth: 3431 feet

Operator License No.: 8628
Op Name: CREDO PETROLEUM CORPORATION
Address: 1801 BROADWAY # 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	263		

111.51

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/26/2009 1:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: LARRY Company: CREDO PETROLEUM CORPORATI Phone: (303) 297-2200

Proposed Plugging Method: Ordered 180 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 02/26/2009 4:30 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 3400' w/25 sxs.
2nd. Plug at 635' w/25 sxs.
3rd. Plug at 320' w/90 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

INVOICED

DATE 3-12-09
INV. NO. 2009061318

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP


RECEIVED

MAR 12 2009

KCC WICHITA

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

FEB 26 2009

PKT