

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20119-00-00
Spot: NENESE Sec/Twnshp/Rge: 30-15S-42W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: KRAUTKRAMER Well #: 1-30
County: WALLACE Total Vertical Depth: 5300 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	5258	0	w/125 sxs cmt
SURF	8.625	424	0	w/250 sxs cmt

172.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/31/2008 8:30 AM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: ED LOEB Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Plugging Method: Ordered 475 sxs 60/40 pozmix - 4% gel - 800# hulls - 3 sxs c.c.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2009 1:10 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 424' w/250 sxs cement.
5 1/2" production casing set at 5258' w/125 sxs cement.
Multi-stage collar at 1945' w/500 sxs cement.
RTD 5300'. PBD 5226'. Perforations at 5120' - 5129'. Stone Corral at 2765'.
Tubing sanded in hole at 3000'. Ran tubing to 2960'.
Connected to tubing - pumped 200 sxs cement mixed with 3sxs c.c. and 600# hulls.
Pulled tubing to 2000' - pumped 200 sxs cement mixed with 200# hulls - cement to surface.
Pulled tubing to surface.
Connected to 8 5/8" surface casing - pumped 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 450#.
Connected to 5 1/2" production casing - pumped 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 0#.

Perfs:

INVOICED
DATE 3-12-09
INV. NO. 2009061320

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 06 2009
CONSERVATION DIVISION
WICHITA KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #043878.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

MAR 03 2009

PKT

10/28/87
 10/24/87
 10/31/87
 01/06/88
 01/25/89

replacement card

TRANS-WESTERN OPERATING COMPANY
 GOLDEN, CO. 80202

30-15 -42W
 NE NE SE

#1-30 KBAUTKBAMER

site: 10 N & 2-3/4 W OF WESKAN, KS city: WALLACE API 15-199-20119
 contr: MURFIN DRILLING COMPANY field: STOCKHOLM SW EXT (1/8 W)
 genl: W. E. KENDALL

fr date 10/28/87 spd date 10/24/87 drig comp 10/31/87 card issued 01/06/88 last revised 01/25/89

E.l.v. 3900 KB LOG	
tops.....	depth/datum
SC.....	2765 +1135
HEEB.....	4122 -222
LANS.....	4179 -279
MRW SH.....	5020 -1120
MRW SD.....	5120 -1220
STE GEN.....	5165 -1265
PBTD.....	5226 -1326
RTD.....	5300 -1400

IP status:
 OIL, P 70 BO & 15 BWPD, MRW 5120-5129,
 INFO RELEASED: 1/25/89 - WAS OIL WELL - TIGHT HOLE
 CSG: 8-5/8" 424 / 250 SX, 5-1/2" 5258 / 125 SX
 NO CORES OR DSTS
 MICT - CO, PF (MRW SD) 5120-5129, W / 4 SPF, AC 250
 GAL 7-1/2% MSR), FRAC 516 BBL GEL 2% KCLW &
 22,500# 20/40 SD, GSO, SET 2-7/8" TBG (DEPTH NA),
 POP, P 70 BO & 15 BWPD (GR 42), 11/24/87

COPYRIGHT 1989
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS