

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00794-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 16-17S-8W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: RATHBUN A Well #: 4
County: ELLSWORTH Total Vertical Depth: 3268 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3268		75 SX
SURF	8.625	204		140 SX

106.21

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2009 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 02/18/2009 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND OPEN HOLE TO 3130' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1050', 750', AND 250'. RUN TUBING TO 1050' AND PUMP 15 SX'S GEL FOLLOWED BY 35 SX'S CEMENT. PULL TUBING TO 750' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 250' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 60' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. TOPPED OFF AGAIN ON 2-20-2009 WITH 30 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3188	3228		

INVOICED
DATE 3-12-09
INV. NO. 2009061321

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 03 2009

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-35292. LOG TECH 5625.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK

PKT