

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23553-00-00  
Spot: NESESWSE Sec/Twnshp/Rge: 15-14S-15W  
370 feet from S Section Line, 1630 feet from E Section Line  
Lease Name: MERMIS Well #: 1  
County: RUSSELL Total Vertical Depth: 3266 feet

Operator License No.: 33315  
Op Name: MAR-LOU OIL CO., LLC  
Address: PO BOX 218  
WILSON, KS 67490

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	250		

106.15

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2008 6:00 AM  
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC  
Proposal Rcvd. from: GARY BUDIG Company: MAR-LOU OIL CO., LLC Phone: (785) 658-2246

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 12/22/2008 8:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 895' w/40 sxs. 2nd. Plug at 350' w/80 sxs. 3rd. Plug at 40' w/10 sxs. Rathole with 30 sxs. Mousehole with 15 sxs.
--

Perfs:

**INVOICED**  
DATE 3-12-09  
INV. NO. 2009061323

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 03 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: DP

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

FEB 27 2009

APST