

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Herman L. Loeb  
Address: P O Box 838  
Phone: (618) 943-2227 Operator License #: 3273  
Type of Well: ENRH Docket #: E-23,285  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 1/16/09 (Date)  
by: Case Morris (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
LKC "D" Depth to Top: 3318 Bottom: 3348 T.D. 3626  
LKC "F" Depth to Top: 3403 Bottom: 3421 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

19101

API Number: 15-009-~~1588~~-00-01  
Lease Name: Sandrock Unit  
Well Number: C-1  
Spot Location (QQQQ): \_\_\_\_\_ - SW - SW - NW  
2310' Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 27 Twp. 20 S. R. 13  East  West  
County: Barton  
Date Well Completed: 11/01/52  
Plugging Commenced: 1/19/09  
Plugging Completed: 1/19/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing Kansas City	Oil	0	226'	8 5/8"	226 ft	None
		0	3524'	5 1/2"	3524 ft	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate 2 holes @ 1600' and 2 holes @ 725'. Run 2 7/8" tubing to 3200'. Pump 14 sk of gel, spot 60 sk of cement w/ 200# hulls from 2600' to 3225'.  
Pull tubing to 1600', pump 100 sk cement w/ 150# hulls from 600' to 1600'. Pull tubing to 800', pump 100 sk of cement w/ 150# hulls from 0' to 800'.  
Pull tubing, hook up to 5 1/2" casing, pump 20 sk cement down 5 1/2" casing, cement circulates to surface out 8 5/8" casing. Shut in casing.  
Cut casing off 4' below ground level, backfill & cleanup location.

Name of Plugging Contractor: Pratt Well Service License #: 5893  
Address: P O Box 847 Pratt, KS 657124-0847

Name of Party Responsible for Plugging Fees: Herman L. Loeb  
State of Illinois County, Lawrence, ss.

George A. Payne (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) George A. Payne  
(Address) P O Box 743 Newburgh, IN 47629-0743

SUBSCRIBED and SWORN TO before me this 13th day of February, 2009  
Michael J. Klopfenstein My Commission Expires: 09/14/2014

Notary Public  
MICHAEL J. KLOPFENSTEIN  
NOTARY PUBLIC  
WARRICK COUNTY, INDIANA  
COMMISSION EXPIRES 9/14/2014

KANSAS CORPORATION COMMISSION  
FEB 20 2009  
CONSERVATION DIVISION  
WICHITA, KS

*[Handwritten initials]*