

MRF 15-065-02865-0000

THE TEXAS COMPANY—LOG OF WELL
OKLAHOMA DIVISION

640 ACRES
N

INDICATE EXACT WELL LOCATION & LEASE BOUNDARY WITHIN SECTION

WELL Robert McKinley #4 L. D. FILE NO. 140336

LOC. SE NE NE SEC. 6 TWP. 9S RGE. 24W

990' from N Line & 330' from E Line of NE/4

DIST. Kansas CO.-PARISH Graham STATE Kansas

COMM. DRLG. 5-24-57 COMP. DRLG. 6-3-57 DAYS DRLG. 11

ROT. FROM 0 TO 3955 CABLE FROM 3955 TO 3956

CONTR. OR CO. RIG NO. Powell Drilling Co. T. D. DRILLED 3956

COMP. T. D. 3956 ZERO ELEV. KB-2448 GRD. ELEV. 2443 CSG. FLG. ELEV. 2440

DATE OF FIRST PROD. 6-10-57 OFFICIAL COMP. DATE 6-11-57

LOGS RUN Halliburton Radiation Guard

CASING RECORD

SIZE INCHES	DEPTH FEET	WEIGHT #/FT.	GRADE	RANGE	REMARKS—QUAN. CMT., TEMP. SURV., ETC.
8-5/8	900	24#	J-55	R-2	New casing, cemented with 510 sacks Pozmix, 2% CC, cement circulated
5-1/2	3948	14#	J-55	R-2&3	New casing, cemented with 100 sacks Pozmix, 1% gel around shoe and 80 bbls Kenpack thru DV tool at 2171'. BH-KB 7.5'; BH-GL 3' Centralizers: 3926, 3852, 3760, 3690, 2161, 850

COMPLETION DATA

FORMATION	<u>Lansing</u>			
DATE OF TEST	<u>6-11-57</u>			
DEPTH OF PROD. INTERVAL	<u>Open Hole 3948-56'</u>			
INITIAL PRODUCTION:				
OIL - BPD	<u>124/8 hrs</u>			
GAS - MCF				
WATER - BPD	<u>None</u>			
GOR				
BHP - PSI				
CORRECTED API GRAVITY	<u>420</u>			
PRODUCING CONDITIONS	<u>Swabbing</u>			
ARTIFICIAL STIMULATION	<u>See Remarks</u>			

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1972
CONSERVATION DIVISION
Wichita, Kansas

REMARKS

WELL Robert McKinley FIELD Holley Pool AREA Russell