

15-065-01631-0000

February 6, 1962

Glickman Oil Company
Box 3104, Washington Street Station
Wichita, Kansas

Houston Oil Company
912 Central Building
Wichita, Kansas

Re: Glickman Oil Co. & Houston Oil Co.
Drilling #1
NW SE NE, Section 5-9S-25W
Graham County, Kansas

Gentlemen:

Samples and drilling time on the above captioned well were saved and examined from 3500 feet to 4045 feet (rotary total depth).

Commenced: 1-25-62	Elevations: 2524 KB, 2521 DF, 2519 GL
Completed: 2-3-62	Surf. Csg: 8-5/8" @ 206' w/150 sx.
Contractor: Glickman Oil Co.	Prod. Csg: 5 1/2" @ 4044' w/125 sx.

The following tops were determined from sample analysis and electrical log (Welex-Radiation Guard). All measurements were taken from the top of the rotary bushing.

FORMATION	SAMPLE	LOG
Anhydrite	2219 (+ 305) Dr1.	2212 (+ 312)
Heebner	3759 (-1235)	3759 (-1235)
Toronto	3780 (-1256)	3779 (-1255)
Lansing	3794 (-1270)	3794 (-1270)
Base Kansas City	4025 (-1501)	4026 (-1502)
Total Depth	4045 (-1521)	4046 (-1522)

SAMPLE DESCRIPTION AND TESTS

TORONTO - 3779 (-1255)

3779-3787	Limestone, light gray-buff, slightly mottled, fossiliferous, trace glauconitic, trace vugular porosity. No shows.
-----------	---

LANSING - 3794 (-1270)

3794-3804	Limestone, cream-white & buff, chalky, fossiliferous. <u>No shows.</u>
3827-3834 (40' Zone)	Limestone, buff, medium-coarse crystalline, slightly oolitic, fossiliferous, good stain and saturation, fair-good crystalline porosity, slight odor. Good show free oil.