

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Edward P. Leiker API NO. 15-065-21457-0000  
 ADDRESS Box 335 COUNTY Graham  
Hays, KS 67601 FIELD EMOR  
 \*\*CONTACT PERSON Edward P. Leiker LEASE Werth T-B A'  
 PHONE 913-625-5310 RT  
 KCC

PURCHASER Mobil Oil Company WELL NO. 1  
 ADDRESS \_\_\_\_\_ WELL LOCATION SW SE NW

DRILLING CONTRACTOR "Emphasis" Oil Operations the NW 1/4 SEC. 34 TWP. 9S RGE. 25W  
 ADDRESS Box 506

ADDRESS Russell, KS 67665


PLUGGING CONTRACTOR \_\_\_\_\_

ADDRESS \_\_\_\_\_

TOTAL DEPTH 4085 PBTD \_\_\_\_\_

SPUD DATE 8-5-81 DATE COMPLETED 8-12-81

ELEV: GR 2546 DF 2548 KB \_\_\_\_\_



WELL PLAT  
 (Quarter) or (Full) Section - Please indicate.

KCC   
 KGS   
 MISC. \_\_\_\_\_

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS  
 Report of all strings set - surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 3/4	8 5/8	21 #	230	Common	155	3%
Production	7 7/8	5 1/2	14 #	4083	Common	150	STATE

RECEIVED  
 12-21-81  
 DEC 21 1981

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2 per ft.	DP 2 Per ft.	3972 - 76
Size	Setting depth	Pecker set at	2 per ft.	DP 2 per ft.	4002 - 4006
2 3/8	4050		2 per ft.	DP 2 per ft.	4044 - 46

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
15% acid - 1000 gal.	3972 - 76
15% acid - 1000 gal	4002 - 4006
15% acid - 500 gal.	4044 - 46

TEST DATE: <u>8-28-81</u>	PRODUCTION <u>KC</u>
Date of first production <u>9-25-81</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	A.P.I. Gravity
Oil <u>6</u> bbls.	Gas <u>30</u> bbls.
Water <u>50</u> %	Gas-oil ratio
Disposition of gas (vented, used on lease or sold)	Producing interval(s) <u>3972-76 &amp; 4002-4006-4044-46</u>

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

CAROL HARRIS  
 Ellis County, KS  
 Notary Public

Name of lowest fresh water producing stratum Sand Depth 60 Ft  
 Estimated height of cement behind pipe Surface

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heeb	3805	-1250		
Lansing	3844	-1290		
B A C	4075	-1524		
T D	4085	-1533		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

**A F F I D A V I T**

STATE OF Kansas, COUNTY OF Ellis SS,  
Edward P. Leiker OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS  
 OATH, DEPOSES AND SAYS:

THAT HE IS \_\_\_\_\_ FOR \_\_\_\_\_  
 OPERATOR OF THE Worth 1-B LEASE, AND IS DULY AUTHORIZED TO MAKE THIS  
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. \_\_\_\_\_ ON SAID LEASE HAS  
 BEEN COMPLETED AS OF THE 16 DAY OF Dec. 19 81, AND THAT ALL  
 INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Edward P. Leiker

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16<sup>th</sup> DAY OF December 19 81

Carol Harfmann  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: 10-14-83

