



Operator Name: Horseshoe Operating, Inc. Lease Name: Householder Well #: 3-29  
 Sec. 29 Twp. 20 S. R. 40  East  West County: Greeley

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i>  Samples Sent to Geological Survey <input type="checkbox"/> Yes <input type="checkbox"/> No  Cores Taken <input type="checkbox"/> Yes <input type="checkbox"/> No Electric Log Run <input type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i>  List All E. Logs Run:  <b>Compensated Density/Neutron</b>	<input type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample  <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%;">Name</td> <td style="width:20%;">Top</td> <td style="width:20%;">Datum</td> </tr> <tr> <td>Base Stone Corral</td> <td>2403'</td> <td>+1200</td> </tr> <tr> <td>Top Winfield</td> <td>2803'</td> <td>+800</td> </tr> <tr> <td>Base Winfield Porosity</td> <td>2825'</td> <td>+778</td> </tr> </table>	Name	Top	Datum	Base Stone Corral	2403'	+1200	Top Winfield	2803'	+800	Base Winfield Porosity	2825'	+778
Name	Top	Datum											
Base Stone Corral	2403'	+1200											
Top Winfield	2803'	+800											
Base Winfield Porosity	2825'	+778											

CASING RECORD <input type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4	8-5/8	24#	238	C	175	2% cc/Flocele
Production	7-7/8	4-1/2	10.5#	2848	C	425	Lite
Production	7-7/8	4-1/2	10.5#	2848	C	125	Common

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
1	2789-2799'	500 gals 15% HCL + additives	
		500 gals 7-1/2% HCL + Pad	
		8000# 20/40 + 4000# 12/20	

TUBING RECORD		Size	Set At	Packer At	Liner Run	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
		2-3/8"	2831			
Date of First, Resumerd Production, SWD or Enhr.			Producing Method			
1/20/05			<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity	
		60	30			

Disposition of Gas	METHOD OF COMPLETION	Production Interval
<input type="checkbox"/> Vented <input checked="" type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	<input type="checkbox"/> Open Hole <input type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	

RECEIVED  
 FEB 28 2005  
 KCC WICHITA

# ALLIED CEMENTING CO., INC. 19046

WR

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Oakley

DATE <u>12-3-04</u>	SEC <u>29</u>	TWP <u>20s</u>	RANGE <u>70w</u>	CALLED OUT	ON LOCATION <u>1:20 PM</u>	JOB START <u>3:40 PM</u>	JOB FINISH <u>4:00 PM</u>
LEASE <u>House Holder</u>	WELL # <u>3-29</u>		LOCATION <u>Tribune S To R&amp;DD 3/4 W 1/4 N</u>		COUNTY <u>Greeley</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR <u>Cheyenne Drlg Rig 11</u>	OWNER <u>Same</u>
TYPE OF JOB <u>Surface</u>	
HOLE SIZE <u>12 1/4</u>	T.D. <u>240'</u>
CASING SIZE	DEPTH <u>241'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT

CEMENT LEFT IN CSG. <u>15'</u>	COMMON <u>175 sks @ 8.85 1548.75</u>
PERFS.	POZMIX @
DISPLACEMENT <u>14 1/2 Bbls</u>	GEL @
	CHLORIDE <u>45 sks @ 30.00 120.00</u>
	ASC @
	<u>P/O Seal 44 \$1 @ 1.40 61.60</u>
	@
	@
	@
	@
	@
	HANDLING <u>179 sks @ 1.25 223.75</u>
	MILEAGE <u>54/sk/mile 671.25</u>
	TOTAL <u>2625.85</u>

**REMARKS:**

Circulated 15 Bbls Cement to pits.

Thank you

CHARGE TO: Horseshoe Operating  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**SERVICE**

DEPTH OF JOB <u>241</u>	
PUMP TRUCK CHARGE	<u>520.00</u>
EXTRA FOOTAGE @	
MILEAGE <u>75 miles @ 4.00</u>	<u>300.00</u>
MANIFOLD @	
@	
@	
	TOTAL <u>820.00</u>

**PLUG & FLOAT EQUIPMENT**

RECEIVED

FEB 28 2005

KCC WICHITA

@  
@

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE Phil Loyd

Phil. p Loyd  
PRINTED NAME

# ALLIED CEMENTING CO., INC. WF 19048

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Oakley

DATE <u>12-5-04</u>	SEC. <u>29</u>	TWP. <u>20s</u>	RANGE <u>40w</u>	CALLED OUT	ON LOCATION	JOB START <u>6:20 PM</u>	JOB FINISH <u>7:00 PM</u>
LEASE <u>House Holder</u>	WELL # <u>329</u>	LOCATION <u>Tribune 13 s 3/4 w n 1/4</u>			COUNTY <u>Creeley</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR Cheyenne Drilling Rig II

TYPE OF JOB Production

HOLE SIZE 7 7/8 T.D. 2848'

CASING SIZE 4 1/2 DEPTH 2857'

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT -

CEMENT LEFT IN CSG. -

PERFS.

DISPLACEMENT 45 1/2 Bbls

OWNER same

CEMENT

AMOUNT ORDERED

4255sk Lite 1/2" Plo Seal

1255sk class C

<u>class C</u>			
<del>COMMON</del>	<u>1255sk</u>	@ <u>10.65</u>	<u>1331.25</u>
POZMIX		@	
GEL		@	
CHLORIDE		@	
ASC		@	
<u>Lite</u>	<u>4255sk</u>	@ <u>7.75</u>	<u>3293.75</u>
<u>Plo Seal</u>	<u>212#</u>	@ <u>1.40</u>	<u>296.80</u>
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>579.5sk</u>	@ <u>1.25</u>	<u>723.75</u>
MILEAGE	<u>54/SK/mile</u>		<u>2171.25</u>
			TOTAL <u>7816.80</u>

EQUIPMENT

PUMP TRUCK CEMENTER Dean/Walt

# 373-281 HELPER Andrew

BULK TRUCK

# 347 DRIVER Mike

BULK TRUCK

# 218 DRIVER Larry

**REMARKS:**

Mix 4255sk Lite 1/2" Plo Seal followed w/ 1255sk class C.

Wash pump & line, release Plug pump Plug 5 BPM. Lite weighed 97 12.6 to 12.8# per sk. Tail 14.1# per sk. Pump pressure 1000#

Landed Plug 1500#, float held. Cement did circulate Thank you

**SERVICE**

DEPTH OF JOB		<u>2848'</u>
PUMP TRUCK CHARGE		<u>1130.00</u>
EXTRA FOOTAGE	@	
MILEAGE	@ <u>7.5 miles</u>	@ <u>4.00</u> <u>300.00</u>
MANIFOLD	@	
	@	
	@	
TOTAL <u>1430.00</u>		

CHARGE TO: Horseshoe Operating

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

**PLUG & FLOAT EQUIPMENT**

<u>1- APF Float Shoe</u>	@	<u>210.00</u>
<u>hatch Down Plug</u>	@	<u>300.00</u>
<u>8-centralizers</u>	@ <u>50.00</u>	<u>400.00</u>
<u>2-Baskets</u>	@ <u>116.00</u>	<u>232.00</u>
	@	

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

RECEIVED TOTAL 1142.00

FEB 28 2005

KCC WICHITA

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE HAWK

PRINTED NAME