

15-065-20044-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name James M. Stewart.

Complete Address: 608 Union Center Building, Wichita, Kansas.

Lease Name Bollig Well No. 1

Location 100' E of CNE-NW Sec. 28 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4075'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company.

Address: Box # 405, Chase, Kansas. License No. 346

Operation Completed: Hour 12:00M Day 7 Month 9 Year 1967

The Above well was plugged as follows:

252'--8 5/8" Surface pipe, cement circulated.

4072'--5 1/2" Production casing cemented with 100 Sx. Well plugged back to 4025'. Top perforations @ 3905'. Dakota section from 1430' to 1610'.

Sanded well back to 3890' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and

squeezed well with 20 sacks gel using 5 sacks hulls in initial gel then followed with 100

Sx. cement, then 22 sacks gel and followed with 20 Sx. cement, then 4 sacks gel and

followed with 8 Sx. cement. Cement from 1630' to 1310'. Gel from 1310' to 270'. Cement

from 270' to 210'. Gel from 210' to 30' and cement from 30' to bottom of cellar. Maximum

pump-in pressure 450#. Final shut-in pressure 200#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
9-12-67
SEP 12 1967

Signed: W. L. Schels
Well Plugging Supervisor

DATE 9/12/67

INV. NO. 6289-U

CONSERVATION DIVISION
WICHITA, KANSAS