

KANSAS

16
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-15-73
FEB 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Bankoff Oil Company,

Complete Address 1119 Sherman, Great Bend, Kansas.

Lease Name Bollig Well No. 5

Location SE-SE-SW Sec. 28 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4035'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 4:30 PM Day 10 Month 2 Year 1973

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 150 Sx.
4034'--5 1/2" Production casing cemented on bottom with 150 Sx.. Well Plugged back to
4000'. Top perforations from 3858' to 3862'..

Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(1300') and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed
with 110 Cu. Ft. cement from 1275' to 950' then 17 sacks gel from 950' to 270' and
followed with 30 Cu. Ft. cement from 270' to 200' then 4 sacks gel from 200' to 40'
and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure
--350#. Final Shut-in Pressure-150#. (Mudding and Cementing by Sun Oil Well Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: *N. J. Orshuk*
Well Plugging Supervisor

INVOICED

DATE 2/16/73
INV. NO. 6975-11