

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-5-69
DEC 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corporation,

Complete Address Suite 1000, Century Plaza, Wichita, Kansas.

Lease Name Sauer Well No. 1

Location CNE-NE Sec. 28 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4100'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor B & B Drilling, Incorporated,

Address 207 Peak Building, Wichita, Kansas. License No.

Operation Completed: Hour 8:00 PM Day 1 Month 12 Year 1969

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1270' and displaced 100 Sx. cement thru
DP from 1270' to 945'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/5/69
INV. NO. 982-W

Signed: M. L. Nichols
Well Plugging Supervisor