

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Received
KCC
Apr 4-1972

Operator's Full Name Bankoff Oil Company,

Complete Address 1119 Sherman, Great Bend, Kansas.

Lease Name Bollig Well No. 1

Location SW-SW-SW Sec. 28 Twp. 9 Rge. (E) (W)25

County Graham Total Depth 4090'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

RTKCC

Other well as hereafter indicated _____

Plugging Contractor South-West Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 2:45 PM Day 31 Month 3 Year 1972

The above well was plugged as follows:

231'--8 5/8" Surface casing, cement circulated with 150 Sx.
4085'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to
4050'. Top perforations from 3861' to 3864'.
Pushed plug to 3850', sanded well back to 3825' and set 4 Sx. cement with dump bailer.
Pulled 4 1/2" casing (1190') and squeezed well initially with 5 sacks hulls and 9 sacks
gel and followed with 110 Cu. Ft. cement from 1275' to 950' then 17 sacks gel from
950' to 270' and followed with 30 Cu. Ft. cement from 270' to 195' then 4 sacks gel
from 195' to 35' and finally 10 Cu. Ft. cement from 35' to bottom of cellar. Maxi-
mum pump-in pressure-200#. Final shut-in pressure-50#. (Mudding and cementing oper-
ations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 4-4-72

INV. NO. 5485-W