

KANSAS

*4*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Brungardt Well No. 1

Location E2 E2 CNE/4 Sec. 32 Twp. 9 Rge. (E) (W) 25  
RTKCC

County Graham Total Depth 4107  
4087! RTKCC

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Barnes & Sons Pipe Pulling Company,

Address Box #313, Russell, Kansas, License No. 9

Operation Completed: Hour 9:45 PM Day 7 Month 7 Year 1969

The above well was plugged as follows:

195'--8 5/8" Surface casing, cement circulated.

4006'--5 1/2" Production casing cemented on bottom with 125 Sx.-- Top perforations @ 3902'.  
RTKCC

Sanded well back to 3875' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with 100  
Sx. cement from 925' to 600' then 11 sacks gel from 600' to 160' and followed with  
20 Sx. cement from 160' to 100' then 3 sacks gel from 100' to 30' and finally 10 Sx.  
cement from 30' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in  
pressure-100#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION  
7-16-69  
JUL 16 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: *W. L. Nichols*  
Well Plugging Supervisor

7/16/69  
96-w