

J
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-26-70
OCT 26 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Incorporated.

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Pfeifer Well No. 1

Location CSW-NW-NW Sec. 32 Twp. 9 Rge. (E) (W)25

County Graham Total Depth 4090'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 6:00 PM Day 22 Month 10 Year 1970

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 175 Sx. (6 3/4" Hole).
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 65 Sx. cement thru
DP from 1325' to 1000'. Pulled DP to 220' and displaced 20 Sx. cement thru DP from
220' to 160'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. S. Nichols
Well Plugging Supervisor

DATE 10/26/70
INV. NO. 2753-W