

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leben-Bankoff,

Complete Address Drawer #2479, Tulsa, Oklahoma.

Lease Name Brungardt Well No. B-1

Location NE-NE-SE Sec. 32 Twp. 9 Rge. (E) (W)25

County Graham Total Depth 4115'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 4:00 PM Day 8 Month 10 Year 1970

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru
DP from 1300' to 975'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 10-12-70

INV. NO. 2668-W