

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
7-20-70
JUL 20 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Herndon Drilling Company

Complete Address Box 489 Tulsa, Oklahoma 74101

Lease Name Rome Well No. 1

Location SE SE NW Sec. 34 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4100'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour Day 18th Month 7 Year 1970

The above well was plugged as follows:

Total Depth 4100' 8 5/8 csg set at 250' cwc. *293 RT KCL*

5 1/2 csg set at 4100' cw 150 sk cmt.

5 1/2 csg Perf. ~~4006'~~ 4016'

Filled 5 1/2 csg W/sd (3950-4100) Dumped 5 sk cmt W/dump bailer. (3900-3950)

Cutoff and recovered 700' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/2 sk hulls, 50 sk reg poz 6% gel,

10 sk gel, plug and 50 sk reg poz 6% gel.

Cmt. (0-240) Gel (240-640) Cmt. (640-880) Gel (880-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 7/20/70

INV. NO. 2953-U