

15-065-01645-0000

Form CP-3
Rev. 6-4-68

KANSAS

Handwritten initials

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Inc.

Complete Address Box 352 Russell, Kansas

Lease Name Rome Well No. 1

Location SW NW Sec. 34 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4045

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 11:30A Day 6 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 4045' 8 5/8 csg set at 160' cwc 100 sk.

4 1/2 csg set at 4041' cw 100 sk cmt.

4 1/2 csg perf. (4032-4036)

Filled 4 1/2 csg W/sd (4000-4045) Dumped 4 sk cmt W/dump bailer. (3960-4000)

Cutoff and recovered 1250' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/4 sk hulls, 70 sk 50-50 poz cmt

6% gel, 15 sk gel W/1 sk hulls, plug and 50 sk 50-50 poz cmt 6% gel.

Gmt. (0-200) gel (200-800) cmt (800-1100) gel (1100-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bob F. Manning
Well Plugging Supervisor

DATE 9/8/69
INV. NO. 418-W