

KANSAS

*Y*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
5-7-71  
MAY 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Spies Well No. 1

Location SE-SE-NE Sec. 35 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3836'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 9:00 PM Day 28 Month 4 Year 1971

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 100 Sx. cement thru  
DP from 1125' to 800'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 5/7/71  
INV. NO. 3054-W