

15-051-23073-00-00

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-23,073-00-00 R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Murfin Drilling Co.

Complete Address 617 Union Center Bldg., Wichita, Ks. 67202

Lease Name Hosley Well No. 1-19

Location 500' FSL - 1980' FEL Sec. 19 Twp. 11 Rge. 19 (East) (West) (West)

County Ellis Total Depth 3770'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co.

Address 617 Union Center Bldg., Wichita, Ks. 67202 License No. _____

Operation Completed: Hour: 3:30 PM Day: 19 Month: 8 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

RECEIVED
STATE CORPORATION COMMISSION
8-24-1982
AUG 24 1982
CONSERVATION DIVISION
Wichita, Kansas

8 5/8" - 218' SP. cas. w/165 sacks common - 2% Gel, - 3% Cal. Cl.

Ordered 170 sacks 50% pozmix - 6% Gel, - 3% Cal. Cl. + 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs.

1st plug @ 825' w/100 sacks.

2nd plug @ 243' w/40 sacks.

3rd plug - Solid bridge of shells + plug @ 40' w/10 sacks.

Circulate 10 sacks in rat hole & 10 sacks in Mouse hole.

Amount of Surface Casing: 218' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent
OIC

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

[Large handwritten X]

Signed: _____
Conservation Division Agent

INVOICED
DATE 9-8-82
INV. NO. 1030-W