

15-051-30405-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1966
12-19-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name J. A. Allison et al

Complete Address: 1528 Wichita Plaza Wichita, Kansas

Lease Name Vine Well No. 1

Location NE NW SE Sec. 11 Twp. 11 Rge. 19 (E) (W) X

County Ellis Total Depth 3585'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sage Drilling Company Inc.,

Address: Wichita, Kansas License No.

Operation Completed: Hour 3 A Day 16 Month 12 Year 1966

The Above well was plugged as follows:

RTD 3585 8 5/8 csg set at 212' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 25 sc cem.

thru drill pipe, Heavy mud to 200' set cementing plug and displaced 20 sc cem. thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cem. to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Pro Massey
Well Plugging Supervisor

DATE 12/19/66
INV. NO. 4446-4