

15-051-20432-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

40

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Robt. R. Price & Aspen Drlg.

Complete Address: Box 783 Great Bend, Kansas

Lease Name Gasaway Well No. 1

Location NW NE SW Sec. 11 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3562

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Aspen Drlg.

Address: Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 3A Day 9 Month 5 Year 1969

The Above well was plugged as follows:

RTD 3562' 8 5/8 csg set at 200' cwc 160 sk. Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE \_\_\_\_\_

INV. NO. \_\_\_\_\_