

15-051-01199-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 23-29

LOCATION NE NE NW

SEC. 11 TWP. 11 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Gassaway 403 Schweiter Bldg.

Operator Okmar Oil Co Address Box 623 Wichita, Kans

Field _____ County Ellis

Total Depth 3685 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 157' circulated with cement - 5 1/2" at 3672'

filled with cement to 3611', ~~max~~ top perf at 3540',

mud to 3050', set 4 sax cement with dump, bailer, pulled

2552' 5 1/2", filled hole with heavy mud to 157', set rock

bridge and 20 sax cement, filled with mud to 30', set 10 sax.

cement to bottom cellar.

SEP 21 1950
9-21-1950

PLUGGING
FILE SEC 11 T 11 R 15W
BOOK PAGE 23 LINE 29

J. P. [Signature]
District Conservation Agent

Date 9-10-50