

15-051-03599-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NW

SEC. 3 ~~13~~ TWP. 11 RGE. 19W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Falconberry ~~Falconberry~~ **FALCONBERRY**

Operator Okmar Oil Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3657 Feet.

Plugging Contractor R & S Pipe Pulling Co

Plugging Contractor's License No. _____ (1)

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 135' circulated with cement - 5 1/2" at 3356' with
200 sax cement behind - Bekerplug and calseal at 3394', perforated
at 3389'.

Filled with sand to 3380', set 5 sax cement with dump bailer,
pulled 2750' 5 1/2", filled with mud to 160', set rock and 15 sax
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 3 T 11 R 19W
BOOK PAGE 11 LINE 12

Stamp: 2-1-1954
FEB 1 - 1954
CONSERVATION DIVISION
WICHITA, KANSAS

District Conservation Agent

Date 1-30-54