



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

RECEIVED
STATE CORPORATION COMMISSION
10-29-1959
OCT 29 1959

CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date Oct 15, 1959, authorized the following plugging operation:

Operator's Full Name: Burch Drilling Co

Complete Address: 1011 Union Cent Wichita Kans.

Lease Name: Mc Call Well No. 1

Location: C Se Tw Sec. 2 Twp. 11 Rge. 23 (E) (W)

County:rego Total Depth: 3815

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits circulate hole with heavy mud, set cementing plug at 500 ft. and displace 20 sac cement thru drill pipe, heavy mud to 180 ft set cementing plug, and displace 20 sac cement, heavy mud to 40 ft set and tie cementing in place with wire, dump 2 sac hulls and displace 10 sac cement, cementing to base of cellar.

Very truly yours,
Gilbert P. Leiker

Signed: Gilbert P. Leiker
Conservation Division Agent