



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION  
8-16-1973  
AUG 16 1973

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. D. B. Pulley guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Schaben Well No. 1

Location: CSE-NW Sec. 3 Twp. 11 Rgs. (E)(W) 23

County: Trego Total Depth 3800' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

204'--8 5/8" Surface casing, cement circulated with 140 Sx.  
3799'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to 3744'. Top of perforations from 3628' to 3632'. Push plug to 3600', sand back from 3600' to 3580' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks hulls and 150 Cu. Ft. cement, staged.

Very truly yours,

H. L. Dehols  
Conservation Division Agent