



15-195-20165-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
7-31-1970  
JUL 31 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Warren Davis of Hellar Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Company,

Complete Address: 117 Cameron Building, Oklahoma City, Oklahoma.

Lease Name: Walker Well No. 1

Location: SW-NE-SW Sec. 7 Twp. 11 Rge. (E)(W)23

County: Trego Total Depth 3870' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent