

15-051-01462-00-00

DISTRICT CONSERVATION AGENT'S REPORT

X

TO:

State Corporation Commission
Conservation Division
800 Biting Building
Wichita, Kansas

FILE NO. 29-20

LOCATION SE SE NW

SEC. 10 TWP. 11 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Haller _____

Operator Chet Loving Address Russell, Kans

Field Burnett West County Ellis

Total Depth 3442 Feet.

(Describe briefly the manner in which the well was plugged)

13" at 977', 8 5/8" at 2918', 5 1/2" at 3298'.

Filled with mud and chat to 3210', perf at 3200' squeezed at

3200' with 15 sax cement. top perf at 3047', ~~filled with~~

~~chat and mud~~, pulled 3127' 5 1/2", filled with mud and chat

to 2900', set 6 sax cement with dump bailer, pulled 1400'

8 5/8" and 471' 13", filled hole with mud to 250', set rock

bridge and 25 sax cement, filled with heavy mud to 25' set rock

bridge and 20 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
10-20-1950
OCT 20 1950

J. P. [Signature]
District Conservation Agent

Date 10-18-50

PLUGGING
FILE SEC 10 T 11 R 18
BOOK PAGE 29 LINE 20