

15-051-30644-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 55-6
LOCATION SW SE SW
SEC. 28 TWP. 11 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Fisher

Operator C & G Drg Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3635 Feet.

Plugging Contractor C & G Drg Co & Globe Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 181' circulated with cement - 5 1/2" at 3629' with

100 sax cement behind - DV tool set at 1379' and circulated

with cement from 1379 to 0'.

Pumped 30 sax Gel followed by cementing plug and 40 sax

cement - found top of cement at 1260' - filled with heavy

rotary mud to 200', set bridge and 5 sax cement, mud to 35',

set rock and filled to 0' with cement.

No pipe recovery.

RECEIVED
STATE CORPORATION COMMISSION
4-27-1956
APR 27 1956

CONSERVATION DIVISION
Wichita, Kansas

Edwin Perry
District Conservation Agent
4-25-56