

*44*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
8-22-1963  
AUG 22 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name B. H. Hilburn  
Complete Address: 1514 Mercantile Bld Dallas, Texas  
Lease Name Miller Well No. 1  
Location SW SW NW Sec. 28 Twp. 11 Rge. (E) (W) 18  
County Ellis Total Depth 3550  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: Tom-Kat Drg Co  
Address: Wichita, Kansas License No.       
Operation Completed: Hour 8AM Day 19 Month 8 Year 63

The Above well was plugged as follows:

8 5/8" 208' circulated with cement.

Circulated hole with heavy mud, set plug at 540', 1/4 sack hulls and  
displaced 20 sax cement through drill pipe, heavy mud to 180', set  
plug, 1/4 sack hulls and displaced 20 sax cement through drill pipe,  
heavy mud to 35', set plug, hulls and filled to bottom cellar with  
cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8/22/63  
INV. NO. 7635-4

Signed: *Edon Petty*  
Well Plugging Supervisor