

15-051-05225-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-15-1960
FEB 15 1960

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

File No. _____ County: Ellis
Location SE SE NE Sec. 28 Twp. 11 Rge. 18 (E) (W) _____
Name of Field: _____ Total Depth: 3600

I have this date completed supervision of plugging of:

Lease Name: Wasinger Well No. 5

Operator's Full Name: Great Bend Pipe & Supply Co

Complete Address: Great Bend, Kans Box 191

Plugging Contractor: R & D Casing Pulling Co

Address: Ellinwood, Kans License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other Well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 5 Month 2 Year 60

The above well was plugged as follows:

8 5/8" 1311' circulated with cement - 4 1/2" 3600' with 200 sax cement behind.

PB to 3563', perforated 3539'

Filled with sand to 3500', set 3 sax cement with dump bailer, pulled

2425' 4 1/2" to 500', circulated hole with heavy mud (Gel) through 4 1/2"

at 500', displaced 20 sax cement through 4 1/2" at 500', heavy mud to 180',

displaced 20 sax cement through 4 1/2" at 180', heavy mud to 35', set

bridge and filled hole to bottom cellar with cement.

Mudding and cementing by R & D Co's pump truck.

Reviewed: J. J. Brock

Signed: [Signature]
Conservation Division Agent

Remarks:

INVOICED
DATE 2/26/60
INV. NO. 982-w