

15-051-05226-00-00



KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: NE SW NE Sec. 28 Twp. 11 Rge. 18 (E) (W) _____

Name of Field: _____ Total Depth: 3668

I have this date completed supervision of plugging of:

Lease Name: Wasinger Well No. 6

Operator's Full Name: Great Bend Pipe & Supply

Complete Address: Box 191 Great Bend, Kansas

Plugging Contractor: R & D Casing Pulling

Address: Ellinwood, Kansas License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour _____ 2PM Day 17 Month 1 Year 61

The above well was plugged as follows:

8 5/8" 1300' circulated with cement - 4 1/2" 3666' with 300 sax cement.

Filled with sand to 3650', set 4 sax cement with dump bailer, pulled

2404' 4 1/2" to 500' circulated hole with heavy mud through 4 1/2" at 500'

(23 sax Gel), displaced 20 sax cement through 4 1/2" at 200', heavy mud to 35',

filled to bottom cellar with cement.

Mudding and cementing by R & D Co pump truck.

RECEIVED
COMMISSION
1-26-1961
JAN 25 1961
CONSERVATION DIVISION
WICHITA, KANSAS

Signed: Edson Perry
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 2/7/61
INV. NO. 2598-W