

15-051-1927-00-00

KANSAS  
STATE CORPORATION COMMISSION

*R*

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 140-22 County: Ellis

Location: NE NE SE Sec. 28 Twp. 11 Rge. 19 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3619

I have this date completed supervision of plugging of:

Lease Name: Fisher Well No. 1

Operator's Full Name: Sinclair Oil Co

Complete Address: Box 551 Chase, Kans

Plugging Contractor: West Supply Co

Address: Chase Kans License No. 14

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_ No \_\_\_

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5Pm Day 24 Month 11 Year 58

The above well was plugged as follows:

8 5/8" 1503' circulated with cement - 5 1/2" 3616' with 150 sax cement behind - P.B. to 3571', perforated 3558'.

Filled with sand to 3540', set 4 sax cement with dump bailer, pulled 2750', 5 1/2" to 500', circulated hole with heavy mud ( gel ) spotted 20 sax cement through 5 1/2" at 500', heavy mud to 180', spotted 20 sax cement through 5 1/2" at 180', heavy mud to 40', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck.

Signed: *Edouard Letty*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 28 T. 11 R. 19 W  
BOOK PAGE 140 LINE 22

RECEIVED  
STATE CORPORATION COMMISSION  
12-2-1958  
DEC 2 - 1958  
CONSERVATION DIVISION  
Wichita, Kansas