

15-051-19226-00-00

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 140-23 County: Ellis

Location: NE NW SE Sec. 28 Twp. 11 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3660

I have this date completed supervision of plugging of:

Lease Name: Fisher Well No. 2

Operator's Full Name: Sinclair Oil Co

Complete Address: Box 551 Chase, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 29 Month 11 Year 58

The above well was plugged as follows:

8 5/8" 1370' circulated with cement - 5 1/2" 3658' with 250 sax cement
behind- P. B. To 3643' - perforated 3622'.

Filled with sand to 3610', set 4 sax cement with dump bailer, pulled
2500' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" (25 sax Gel)
displaced 20 sax cement through 5 1/2" at 600', heavy mud to 200', displaced
20 sax cement through 5 1/2", heavy mud to 35', set bridge and 10 sax cement
to bottom cellar.

Signed: *Edna Petty*
Conservation Division Agent

Reviewed: *J. Laura Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 28 T. 11 R. 18W
BOOK PAGE 140 LINE 23

RECEIVED
STATE CORPORATION COMMISSION
12-9-1958
DEC 9 - 1958
CONSERVATION DIVISION