

15-051-19229-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

*R*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 125-33 County: Ellis

Location: NE NE NE Sec. 28 Twp. 11 Rge. 18 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3613

I have this date completed supervision of plugging of:

Lease Name: Shall-Wasinger Well No. 1

Operator's Full Name: Great Bend Pipe & Supply

Complete Address: Box 191 Great Bend, Kans

Plugging Contractor: R & D Casing Pulling Co

Address: Ellinwood, Kans License No. 236

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No \_\_\_\_\_

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3PM Day 30 Month 8 Year 58

The above well was plugged as follows:

8 5/8" 1278' circulated with 600 sax cement - 4 1/2" 3612' with 400 sax cement behind.

Filled with sand to 3500', set 3 sax cement with dump bailer, pulled 2560', 4 1/2" - filled with heavy mud (Gel) to 550', set 20 sax cement at 550', heavy mud (Gel) to 160', set 20 sax cement at 160', heavy mud to 35', set rock and 10 sax cement to 0'.

Signed: *Edward Kelly*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 28 T. 11 R. 18 W  
BOOK PAGE 125 LINE 33

RECEIVED  
STATE CORPORATION COMMISSION  
9-4-1958  
SEP 4 1958  
CONSERVATION DIVISION  
Wichita, Kansas