

15-051-19228-00-00

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 125-35 County: Ellis

Location: NW SW NE Sec. 28 Twp. 11 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3643

I have this date completed supervision of plugging of:

Lease Name: Shell-Wasinger Well No. 8

Operator's Full Name: Great Bend Pipe & Supply

Complete Address: Box 191 Great Bend, Kans

Plugging Contractor: R & D Casing Pulling Co

Address: Ellinwood, Kans License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 5 Month 9 Year 58

The above well was plugged as follows:

8 5/8" at 1357' circulated with 400 sax cement - 4 1/2" 3642' with 200
sax cement behind - P.B. 3610', perforated ~~at~~ 3588'

Filled with sand to 3570', set 3 sax cement with dump bailer, pulled
2360' 4 1/2" - filled hole with heavy mud (Gel) to 400', set rock and
20 sax cement, heavy mud to 200', set bridge and 20 sax cement, heavy
mud to 35', set rock and 10 sax cement to bottom cellar.

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 28 T. 11 R. 18W
BOOK PAGE 125 LINE 35

RECEIVED
STATE CORPORATION COMMISSION
9-10-1958
SEP 10 1958
CONSERVATION DIVISION