
## 15-051-19230-00-00

## KANSAS STATE CORPORATION COMMISSION



TO: Jewel M. Ogden, Director 500 Insurance Building 212 North Market Wichita 2, Kansas

Wichita 2, Kansas	·					
File No.	County:	Ellis				
Location: NE SE NE	Se	c. 28	_Twp11	Rge18	(E)	_(W)
Name of Field:			Total Dept	h: 3629		<del></del>
I have this date completed	-	ugging o	f:		•	
Lease Name: Shell-Was	inger		We	11 No. 2		
Operator's Full Name:	Great Bend Pipe	e & Supp	oly Co			
Complete Address:	Box 191 Great	Bend, I	Kans			
Plugging Contractor:	R & D Casing Pu	ıll <b>i</b> ng		······································		~~~···································
Address:	Ellinwood, Kans	3	Li	cense No.	236	<del></del>
Oil Well X Gas Well	Input We	11	SWD Well	D	& A	····
Other well as hereafter ind	icated:					
Was any delay in plugging o	perations caused	by Conse	rvation Divi	sion Agent?	Yes	_No
If yes how long?		Reason:				
	-					
Operation Completed: Hour_	4PM Day_	2 ·	Month	9	Yea	r 58 .
The above well was plugged	as follows:			•		
8 5/8" 1345' circul	ated with 400 s	BAX COM	ent - 4 <u>1</u> 8	3628! with	200	
sax cement - P.B. t	o 3015', perfor	eated 35	731.			
Filled with sand to	3550¹, set 3 s	sax come	ent with du	ump bailer	, pull	ed
2510' $4\frac{1}{2}$ " - filled	hole with heavy	y mu <b>d (</b>	gel ) set	bridge at	5001	
with 20 sax cement,	heavy mudto 20	00 <b>1,</b> set	bridge ar	nd 20 sax	c emen t	9
heavy mud to 35', s	et rock and 10	sax cen	ment to bot	ttom cella	r.	
			·	, .		
		Signed:	Cedon	Letter		
			Conserva	tion Divisi	on Agent	<u> </u>
06	R = 1/				icsion	

Reviewed:

fluca Wook Field Supervisor

Remarks:

PLUGGING
FILE SEC 26 T 11 R18W
BOOK PAGE 125 LINE 34

CONCECULATION OF THE STATE OF T