

15-051-05223-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 55-42
LOCATION NE SE NW
SEC. 28 TWP. 11 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Truan
Operator Gulf Oil Corp. Address Chase, Kans
Field _____ County Ellis
Total Depth 3597 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1313' circulated with cement - 5 1/2" at 3581' with
100 sax cement behind.

Filled with chat to 3570', set 4 sax cement with dump bailer,
pulled 2920' 5 1/2", mud to 300', set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

STATE CORPORATION COMMISSION
NOV 14 1952

CONSERVATION DIVISION
Wichita, Kansas

Edmund P. [Signature]
District Conservation Agent

Date 11-11-52

PLUGGING
FILE SEC-28 T-11 R-18
NOV 14 1952